WHITLEY COUNTY BOARD OF ZONING APPEALS STAFF REPORT

24-W-VAR-3 DEVELOPMENT STANDARDS VARIANCE

Brooks Langeloh 2740 W. 700 North FEBRUARY 27,2024
AGENDA ITEM: 3

SUMMARY OF PROPOSAL

Current zoning: LR, Lake Residential

Property area: 0.64± Acres

The petitioner, co-owner of the subject property, is requesting development standards variances of the required front and side setbacks and minimum lot width and area as part of a proposed subdivision of the subject property. The site is located at 2740 West 700 North, at the northwest corner of 700 North and Brown Road, in Section 36 of Etna Troy Township. The property is currently improved with a dwelling and shed.

The proposed plat would break the existing U-shaped parcel into two more regular shaped lots. Lot 1 would contain the existing outbuilding, while Lot 2 would have the existing house.

The plat is being considered by the Plan Commission on the 21st, and if approved, it would be conditioned upon variances being granted for lot development standards. This table shows the code standards for each lot and the necessary variances:

	Code	Lot 1	Lot 2	Variance
Minimum lot area	10,000 sq. ft.	11,976 sq. ft.	8,720 sq. ft.	1,280 sq. ft.
Minimum lot width	70'	70'	68.25'	1.75'
Minimum lot frontage	50'	70'	215.63'	NA

Additionally, because the plat dedicates right-of-way for the adjacent public roads, and because there are existing improvements on each lot, setback encroachments are created. Because they are created by the nature of the plat requirements, these encroachments can be treated as legal nonconformances. However, the petitioner wishes to address the nonconformities now to reduce potential future difficulties in using the lots. This table shows the code and proposed setbacks and necessary variances (in bold) for the setback encroachments:

		Front yard	Side yard	Rear yard
Code		35'	5' (current)	15' (primary)
			10' (as proposed)	5' (accessory)
Lot 1	existing	55'±	6'± (north)	NA
			26.5'± (south)	
	proposed	42'±	5'± (north)	
			5'± (south)	
Lot 2	existing	32'± (Brown Road)	27'± (north)	NA
		45'± (700 North)	14'± (west)	
	proposed	17'± (Brown Road)	5'± (north)	
		30'± (700 North)	5'± (west)	

Note that the side yard standard is variable as the code requirement is 5' for existing lots created prior to the adoption of the code in 2006, while it is 10' for lots created after 2006. Since the proposed plat would create new lots, the 10' standard would apply. Also note that the existing parcel and proposed lots both are

considered double frontage/corner lots, which are defined to have two front yards, two side yards, and no rear yard.

For reference, based on the Best Available map information and topography, the structure should not be located in the regulatory floodplain.

REVIEW CRITERIA

Indiana Code §36-7-4-918.5 and Section 10.10 of the Zoning Code state the criteria listed below upon which the Board must base its review. Staff's comments/proposed findings of fact under each criterion.

1. The approval will not be injurious to the public health, safety, morals, and general welfare of the community;

The proposed setback variances will not be injurious to the public health, morals, and general welfare as the proposed setbacks are no different than the setbacks of the existing structures or as currently permitted by the code. Public safety may be affected as the increased rights-of-way could permit road widening that would place public traffic nearer the existing house, particularly along 700 North, but the effect is not likely significant enough to be considered injurious.

The proposed lot variances are also not injurious. The proposed reduced lot width is minimal, being only 1.75'. The reduced lot area of 8,720 sq. ft. is also not injurious as it maintains an area adequate for the residential use, and other lots of lesser area in the vicinity and throughout the LR district exist without particular injurious effects.

2. The use and value of the area adjacent to the property included in the variance will not be affected in a substantially adverse manner; and

The proposed setback variances will not adversely affect the value and use of the area adjacent to the property as the proposed variances would not permit any visible or effective changes to the existing structures.

The proposed lot variances would not substantially affect the value of the surrounding area since the width variance would also reestablish the existing situation, and the lot area variance is comparable to many existing lots in the vicinity. Both variances would allow for adequate room for permitted uses, so the use of the surrounding area would also not be adversely affected.

3. The strict application of the terms of the Ordinance will result in practical difficulties in the use of the property. This situation shall not be self-imposed, nor be based on a perceived reduction or restriction of economic gain.

The strict application of the Ordinance terms would result in practical difficulties for setbacks, as the required dedication of rights-of-way creates encroachments in front setbacks and would leave only a 23' buildable width for Lot 2. Additionally, the side setbacks differ because they are intended to apply to entirely new lots, whereas this site includes existing improvements. This is further reflected in the petitioner's request to maintain the existing 5' side setbacks, even where the existing improvements would be compliant with the 10' setback.

The lot variances also have practical difficulties. The area of Lot 2 could be made compliant by taking a strip from the western side of Lot 1 and the access easement, but such a strip would be useful only for code compliance. Practically, it would become a matter of contention between lot owners and a likely maintenance problem. Other solutions to the lot area would create further variances or encroachments. The lot width request originates, like the setback variances, from the dedication of right-of-way along Brown Road, which is an imposition of the subdivision code.

SUGGESTED CONDITIONS

If the Board moves to grant the variances, the following are suggested condition(s) of the approval:

1. The plat be amended with the setback lines as approved and a notation of this variance approval.


Date report prepared: 2/21/2024

BOARD OF ZONING APPEALS ACTION

Findings of	of Fact	t Crite	ria							
Vote:	Vote: Green Sheiss Wilkinson		W	Wolf Wright						
.]	Yes	No	Yes	No	Yes	No	Yes	No	Yes	No
Criterion 1										
Criterion 2									!	
Criterion 3										
Motion: _	Grai	nt		31.000	e sauta e con		arremorphisms		0.000	
			conditi	ions						
	_ Den	•						В	sy:	
Vote:	Gre	een	She	eiss	Wilki	nson	W	olf	Wr	ght
Yes										
No										
Abstain								100		



WEST LOON (PRELIMINARY)



AREA NOTES
The Plat of West Loon contains 0.64 acres.
Lot Number 1 contains 202 acres (L.75% eq. ft.).
Lot Number 2 contains 0.20 acres (R.720 eq. ft.).
There are 0.17 acres (7.25% eq. ft.) of Dedicated Right-of-Way.

VICINITY MAP

PROPERTY ADDRESS FOR LOT # 2

2740 W 700 N Columbia City, IN 46725

FIELD WORK COMPLETED ON 1-19-2024

P = PLAT
F.X.S = RECONDED
F.X.S = REONT YARD SETBACK
S.X.S = SIDE YARD SETBACK
R.Y.S = REAR YARD SETBACK
U. & D.E. = UTLLTY & DPAINAGE EASEMENT

C = CALCULATED
R = RECORDED

LEGEND M = MEASURED